

CEDAR LAKE MINING, INC.
LITTLE SPRING CREEK - EAST MINE, P-3968

ALABAMA SURFACE MINING COMMISSION
SURFACE MINING PERMIT APPLICATION

PART V
BONDING

Prepared by:

TASK Engineering Management Inc.
P.O. Box 660548
Birmingham, Alabama 35266-0548
Telephone 205.978.5070
[Email: jw-task@charter.net](mailto:jw-task@charter.net)

V. BONDING

A. Site Conditions

1) Briefly describe the conditions within the increment which you are currently proposing to mine by answering the following:

- (a) Average pre-mining slope 10.30%
- (b) Percent sandstone 17.00%
- (c) Final highwall slope (average) (if applicable) 10.00%
- (d) Acres Prime Farmland 0%
- (e) Acres Abandoned Land 0%
- (f) Average pH of topsoil or topsoil substitute 6.00

Note: If pH range over the increment area is greater than one pH unit (unit 1 thru 14), give approximate number of acres which fall within each unit.

- (g) Overburden acid-base account (expressed as tons of calcium carbonate per 1,000 tons material) N/A (only if total sulfur exceeds 0.5%).

B. Estimate of Reclamation Cost (780.18)

Give a detailed estimate of your cost of reclamation for the increment you are currently proposing to mine. Give individual cost estimate for grading, highwall elimination, topsoil (or topsoil substitute) replacement, revegetation and any other cost which may be applicable (prime farmland, hydrologic factors, etc.) **Show Calculations**

V. BONDING

ESTIMATED BOND TOTAL/INC. #1: \$ \$1,013,845.75

Company: Cedar Lake Mining, Inc. License: L-0775 Acreage Fee \$ 35

Permit # P-3968 Type Action: X New Permit

MINE: Little Spring Creek X New Increment Inc. #1

Expiration Date: _____ Revision. Inc. # _____

<u>Acres to be Bonded</u>		Bond #	
<u>212</u> Mining Acres	Current Amount & (Acres)		\$ _____
<u>0</u> Incidentals	After Revision/Review		\$ _____

Comments:

Base Calculations for Mining Acres

Grading	<u>212</u>	Acres @ \$1,500/acre	\$ <u>318,000.00</u>
Revegetation	<u>212</u>	Acres @ \$800/acre	\$ <u>169,600.00</u>

Highwall Elimination

X Drill & Shoot

Highwall Height (Ft) 69 (hw) $(1/2)[(0.5)(hw)(1.5)(hw)](1/27)(hw)(1.00/yd^3)$ \$ 166,635

Backfill

Highwall Length (Ft) 2520 (hw) $(1/2)[(hw)(3)(hw)](1/27)(hw)1.50/yd^3$ \$ -

Adjustments

1.	Grading	212	Acres @ \$250/acre	\$	53,000.00
2.	Topsoil Replacement	0	Acres @ \$500/acre	\$	-
3.	Topsoil Substitute	212	Acres @ \$200/acre	\$	42,400.00
4.	Post-mine Forest	212	Acres @ \$150/acre	\$	31,800.00
5.	Steep Slope' Mining	0	Acres @ \$100/acre	\$	-
6.	Steeper than 4:1 Post-mining slope	0	Acres @ \$100/acre	\$	-
7.	Greater than 50% Sandstone	0	Acres @ \$300/acre	\$	-
8.	Prime Farmland	0	Acres @ \$1,500/acre	\$	-
9.	Adverse PHC	Site Specific		\$	-
10.	Tuscaloosa Formation	0	Acres @ \$300/acre	\$	-

Incidentals

1.	Haul Roads	0.17	Acres @ \$1,000/acre	\$	170.00
2.	Temporary Ponds, Diversions	5	Structures @ \$20,000/Struct.	\$	100,000.00
3.	Permanent Impoundments	0	Structures @ \$10,000/Struct.	\$	-
4.	Permanent Roads	0	Acres @ \$400/acre	\$	-
5.	Coal Stockpiles, Washer & Refuse Disposal Areas	0	Acres @ \$2,000/acre	\$	-
6.	Topsoil Stockpiles	0	Acres @ \$800/acre	\$	-
7.	Removal of Structures				
	Washer/Crusher			\$	-
	Buildings			\$	-
	Equipment			\$	-
	Other (List)			\$	-
			TOTAL INCIDENTAL BOND	\$	100,170.00

Summary of Costs by Category

Mining Area	Base Grading	\$	<u>318,000.00</u>
	Base Revegetation	\$	<u>169,600.00</u>
Adjustments	1. Grading	\$	<u>53,000.00</u>
	2. Topsoil Replacement	\$	<u>0.00</u>
	3. Topsoil Substitute	\$	<u>42,400.00</u>
	4. Forest/Range Land Use	\$	<u>31,800.00</u>
	5. Steep Slope' Mining	\$	<u>0.00</u>
	6. Post-mining Slope	\$	<u>0.00</u>
	7. % Sandstone	\$	<u>0.00</u>
	8. Prime Farmland	\$	<u>0.00</u>
	9. Adverse PHC	\$	<u>0.00</u>
	10. Tuscaloosa Formation	\$	<u>0.00</u>
Highwall Elimination		\$	<u>166,635.00</u>
Incidentals		\$	<u>100,170.00</u>
	Subtotal	\$	<u>881,605.00</u>
	15% Contractor Profit & Overhead	\$	<u>132,240.75</u>
	TOTAL	\$	<u>1,013,845.75</u>

Conditions to Permit which affect Bond Amount

- 1.
- 2.
- 3.
- 4.

ESTIMATED BOND TOTAL/INC. #5: \$ \$8,970.00

Company: Cedar Lake Mining, Inc. License: L-0775 Acreage Fee \$ 35

Permit # P-3968 Type Action: X New Permit

MINE: Little Spring Creek X New Increment Inc. #5

Expiration Date: _____ Revision. Inc. # _____

<u>Acres to be Bonded</u>		Bond #	
<u>2</u> Mining Acres	Current Amount & (Acres)	\$	_____
<u>2</u> Incidentals	After Revision/Review	\$	_____

Comments:

Base Calculations for Mining Acres

Grading	<u>2</u>	Acres @ \$1,500/acre	\$ <u>3,000.00</u>
Revegetation	<u>2</u>	Acres @ \$800/acre	\$ <u>1,600.00</u>

Highwall Elimination

Drill & Shoot

Highwall Height (Ft) 0 (hw) $(1/2)[(0.5)(hw)(1.5)(hw)](1/27)(hw)(1.00/yd^3)$ \$ -

Backfill

Highwall Length (Ft) 0 (hwl) $(1/2)[(hw)(3)(hw)](1/27)(hwl)1.50/yd^3$ \$ -

CEDAR LAKE MINING, INC.
LITTLE SPRING CREEK-EAST MINE, P-3968

Adjustments

1.	Grading	<u>2</u>	Acres @ \$250/acre	\$	<u>500.00</u>
2.	Topsoil Replacement	<u>0</u>	Acres @ \$500/acre	\$	<u>-</u>
3.	Topsoil Substitute	<u>2</u>	Acres @ \$200/acre	\$	<u>400.00</u>
4.	Post-mine Forest	<u>2</u>	Acres @ \$150/acre	\$	<u>300.00</u>
5.	Steep Slope' Mining	<u>0</u>	Acres @ \$100/acre	\$	<u>-</u>
6.	Steeper than 4:1 Post-mining slope	<u>0</u>	Acres @ \$100/acre	\$	<u>-</u>
7.	Greater than 50% Sandstone	<u>0</u>	Acres @ \$300/acre	\$	<u>-</u>
8.	Prime Farmland	<u>0</u>	Acres @ \$1,500/acre	\$	<u>-</u>
9.	Adverse PHC	Site Specific		\$	<u>-</u>
10.	Tuscaloosa Formation	<u>0</u>	Acres @ \$300/acre	\$	<u>-</u>

Incidentals

1.	Haul Roads	<u>2</u>	Acres @ \$1,000/acre	\$	<u>2,000.00</u>
2.	Temporary Ponds, Diversions	<u>0</u>	Structures @ \$20,000/Struct.	\$	<u>-</u>
3.	Permanent Impoundments	<u>0</u>	Structures @ \$10,000/Struct.	\$	<u>-</u>
4.	Permanent Roads	<u>0</u>	Acres @ \$400/acre	\$	<u>-</u>
5.	Coal Stockpiles, Washer & Refuse Disposal Areas	<u>0</u>	Acres @ \$2,000/acre	\$	<u>-</u>
6.	Topsoil Stockpiles	<u>0</u>	Acres @ \$800/acre	\$	<u>-</u>
7.	Removal of Structures				
	Washer/Crusher			\$	<u>-</u>
	Buildings			\$	<u>-</u>
	Equipment			\$	<u>-</u>
	Other (List)			\$	<u>-</u>

	TOTAL INCIDENTAL BOND	\$	<u>2,000.00</u>
--	-----------------------	----	-----------------

Summary of Costs by Category

Mining Area	Base Grading	\$	<u>3,000.00</u>
	Base Revegetation	\$	<u>1,600.00</u>
Adjustments	1. Grading	\$	<u>500.00</u>
	2. Topsoil Replacement	\$	<u>0.00</u>
	3. Topsoil Substitute	\$	<u>400.00</u>
	4. Forest/Range Land Use	\$	<u>300.00</u>
	5. Steep Slope' Mining	\$	<u>0.00</u>
	6. Post-mining Slope	\$	<u>0.00</u>
	7. % Sandstone	\$	<u>0.00</u>
	8. Prime Farmland	\$	<u>0.00</u>
	9. Adverse PHC	\$	<u>0.00</u>
	10. Tuscaloosa Formation	\$	<u>0.00</u>
Highwall Elimination		\$	<u>0.00</u>
Incidentals		\$	<u>2,000.00</u>
	Subtotal	\$	<u>7,800.00</u>
	15% Contractor Profit & Overhead	\$	<u>1,170.00</u>
	TOTAL	\$	<u>8,970.00</u>

Conditions to Permit which affect Bond Amount

- 1.
- 2.
- 3.
- 4.